


speed|cook|



PREFAB MOBILE SITE KITCHENS CONFIGURED AND EQUIPPED TO YOUR SPECIFICATIONS

Speedcook prefab mobile kitchens/cafeterias are fully equipped with all appliances and fittings required for the hygienic preparation of delicious meals on site. These attractive, prefab mobile kitchen units are easy to use, clean and keep tidy, no matter how remote your site happens to be. Our Speedcook portable prefab kitchen units are configured and equipped according your site requirements. If on-site meals are still unappealing, blame the cook – not the Speedcook mobile kitchen!

SPEEDCOOK

GENERAL CONSTRUCTION

Units that are 6, 9 and 12 m in length:

Full-length, full-width structurally welded steel chassis with two 175 x 50 mm lipped-channel, longitudinal beams. Outriggers and cross-members are of 75 x 38 mm channel.

Units that are 15 and 18 m in length:

Full-length, full-width structurally welded steel chassis with two 250 x 75 mm lipped-channel, longitudinal beams. Outriggers and cross-members are of 75 x 38 mm channel.

The complete assembly is sandblasted and coated with self-etch red oxide primer. For added protection, the chassis is coated with a waterproof, malleable compound called Plaswax or similar which forms a tenacious wax-like surfacing.

ROOF AND CEILING CONSTRUCTION

The roof is a pitched roof construction consisting of the following:

- Roof exterior is galvanised sheeting
- Ceiling insulation is 40 mm thick high-density foam sandwiched between 0,5 mm white chromadek sheeting
- Ceiling finish is 0,5 mm white chromadek ceiling.

SIDEWALL CONSTRUCTION

The standard exterior and interior finish is 0,5 mm Chromadek, which is a galvanised, prepainted (frost-white) finish. The perimeter and internal walls are fully insulated with 40 mm thick high-density foam. As an optional extra, chromadek sheeting with a decorative woodlike finish can be used for internal wall finishes.

WINDOWS

All window frames are aluminium, top-hung and fitted with 4 mm thick glass. The area of the windows is equal to or greater than 10% of the gross floor area of each habitable room.

FLOOR CONSTRUCTION

Treated timber floorboards, 18 mm thick, are glued and screwed to cross-members and covered in 2 mm industrial vinyl welded at joints. Carpet covering optional extra.

ELECTRICS

Units are wired for connecting to 220 volt supply, in accordance with SABS 0142:1987, and are fitted with earth-leakage protection and distribution board. Lights, plugs, geyser and interior electrical fittings are installed as shown on the layout diagrams.

PLUMBING

Copper, stainless steel, or Polycop piping is used for water supply, and PVC fittings for sewerage and wastewater.

TRANSPORT AND HANDLING

It is extremely important that the following points are taken into consideration before delivery can be effected:

- Site should be level and compacted. It should not slope more than 200 mm over the length and 100 mm over the width of the unit.
- Site must be accessible for an abnormally large load. All trees and/or other obstacles that may be in the way must be removed beforehand to allow easy access.
- Gates into property must be a minimum of 4 m wide, and truck must have a straight runup of at least 25 m, to allow bigger units (9 m and upwards) to be offloaded into position, and allow trucks to drive out from under unit after having lifted it.
- Unit will be dropped onto trestles and levelled in order to allow doors to open freely. Final levelling must be done by client unless siting is done and charged for by Speedspace.
- A site inspection prior to delivery can be arranged.
- All equipment used for loading and off-loading of units is certified and load tested.

OPTIONAL EXTRAS

- Exterior skirting
- Carpets
- Burglar bars
- Flyscreens for both windows and doors
- Curtains or blinds
- Air conditioner
- Three-phase electrics
- Geysers (gas or electric)
- Kitchen appliances (gas or electric)
- Carports
- Floor insulation
- Other fittings/applications as per customer request.

SPECIFICATIONS

Description	Model S6241	Model 6301	Model S96301	Model S12301	Model S15341	Model S18341
Length (ext)	5 820	5 820	9 300	11 620	15 100	17 420
(int)	5 740	5 740	9 220	11 540	15 020	17 340
Width (ext)	2 420	2 990	2 990	2 990	3 580	3 580
(int)	2 260	2 910	2 910	2 910	3 500	3 500
Height (int)	2 400	2 400	2 400	2 400	2 400	2 400
Electrics Std	Std	Std	Std	Std	Std	
Aluminium windows	Std	Std	Std	Std	Std	Std
Vinyl floor	Std	Std	Std	Std	Std	Std
Wall insulation	Std	Std	Std	Std	Std	Std
Roof insulation	Std	Std	Std	Std	Std	Std

(All dimensions given in mm)



EXTEND YOUR OPTIONS FAST

south africa

beyers naude drive honeydew 2040
tel +27 11 794 1340 fax +27 11 794 1347
e-mail speedspace@speedspace.co.za
website www.speedspace.co.za

botswana

Plot 54060 Phakalane
Gaborone Botswana
tel +267 391 2537 fax +267 391 3879
e-mail speedspace@info.bw



Follow us on

facebook: [speedspace](https://www.facebook.com/speedspace)

twitter: www.twitter.com/speedspacesa